

Part 2 – Work Requirements

Section VIIC - Drawings

Specifications

See separate sections of Volume II:

Section VIIA - General Specification covering the requirements amongst others for Materials and Testing

Section VIIB - Particular Specifications including Scope, Specification for (I) Performance-Based Routine Maintenance Works, (II) Initial Maintenance Works and (III) Emergency Works

Section VIIC - Drawings

Appendix 1 - Guidelines for a Code of Conduct and Action Plan to prevent Gender-Based Violence (GBV) and Violence Against Children (VAC)

Drawings

1. Strip maps for Initial Maintenance Works on Road No. 4011

Road No. 4011 (Junc. Rd 7, B. Phoukhilao - Junc. Rd 7, B. Khangkhai), total length 13.10 Km, Pek district, Xiengkhouang province,										
No	MAC	Description	Ch. (km 0+000 - km 2+500)							
			0+000	0+500	1+000	1+500	2+000	2+500		
1	121	Heavy grading								
2	222	Reshaping the road, incl. ditches			8400					
3	223	Regravelling, 15.0 cm thick								
4	125	Spot filling			250					
5	133	Cleaning of culverts					1			
6	135	Repair of erosion damages								
Ch. (km 2+500 - km 5+000)										
No	MAC	Description	2+500	3+000	3+500	4+000	4+500	5+000		
1	121	Heavy grading								
2	222	Reshaping the road, incl. ditches			17,500					
3	223	Regravelling, 15.0 cm thick								
4	125	Spot filling			400					
5	133	Cleaning of culverts	1					1		
6	135	Repair of erosion damages					100			
Ch. (km 5+000 - km 7+500)										
No	MAC	Description	5+000	5+500	6+000	6+500	7+000	7+500		
1	121	Heavy grading								
2	222	Reshaping the road, incl. ditches		7000			7000			
3	223	Regravelling, 15.0 cm thick								
4	125	Spot filling		150			150			
5	133	Cleaning of culverts				1				
6	135	Repair of erosion damages		50			50			

No	MAC	Description	Ch. (km 7+500 - km 10+000)														
			7+500	8+000	8+500	9+000	9+500	10+000									
1	121	Heavy grading															
2	222	Reshaping the road, incl. ditches			7000									3500			
3	223	Regravelling, 15.0 cm thick															
4	125	Spot filling		150										50			
5	133	Cleaning of culverts										1					
6	135	Repair of erosion damages				75											25

No	MAC	Description	Ch. (km 10+000 - km 12+500)													
			10+000	10+500	11+000	11+500	12+000	12+500								
1	121	Heavy grading														
2	222	Reshaping the road, incl. ditches			10500											
3	223	Regravelling, 15.0 cm thick														
4	125	Spot filling		250												
5	133	Cleaning of culverts										1				
6	135	Repair of erosion damages					125									

No	MAC	Description	Ch. (km 12+500 - km 13+200)													
			12+500	13+000												
1	121	Heavy grading														
2	222	Reshaping the road, incl. ditches		4900												
3	223	Regravelling, 15.0 cm thick														
4	125	Spot filling		70												
5	133	Cleaning of culverts														
6	135	Repair of erosion damages				25										

2. Strip maps for Initial Maintenance Works on Road No. 3905

Road No. 3905 (Junc. Rd 6, B. Pha - Junc. Rd 4011, B. Na Nhong), total length 14.10 Km, Kham district, Xiengkhouang province,

Road No. 3905			Ch. (km 0+000 - km 2+500)					
o/n	MAC	Description	0+000	0+500	1+000	1+500	2+000	2+500
1	121	Haevy grading						
2	222	Reshaping the road, incl. ditches			9000			
3	223	Regravelling, 15.0 cm thick						
4	125	Spot filling			500			
5	133	Cleaning of culverts			1			
6	135	Repair of erosion damages					100	
Road No. 3905			Ch. (km 2+500 - km 5+000)					
o/n	MAC	Description	2+500	3+000	3+500	4+000	4+500	5+000
1	121	Haevy grading						
2	222	Reshaping the road, incl. ditches	2500			9000		
3	223	Regravelling, 15.0 cm thick						
4	125	Spot filling		100			450	
5	133	Cleaning of culverts	1					1
6	135	Repair of erosion damages				100		
Road No. 3905			Ch. (km 5+000 - km 7+500)					
o/n	MAC	Description	5+000	5+500	6+000	6+500	7+000	7+500
1	121	Haevy grading						
2	222	Reshaping the road, incl. ditches			8000			2500
3	223	Regravelling, 15.0 cm thick						
4	125	Spot filling			350			
5	133	Cleaning of culverts					1	
6	135	Repair of erosion damages				50		

ခ/၀	MAC	Description	Ch. (km 7+500 - km 10+000)													
			7+500	8+000	8+500	9+000	9+500	10+000								
1	121	Haevy grading														
2	222	Reshaping the road, incl. ditches		5000			7000									
3	223	Regravelling, 15.0 cm thick														
4	125	Spot filling		150				300								
5	133	Cleaning of culverts				1										
6	135	Repair of erosion damages		50				75								
			Ch. (km 10+000 - km 12+500)													
ခ/၀	MAC	Description	10+000	10+500	11+000	11+500	12+000	12+500								
1	121	Haevy grading														
2	222	Reshaping the road, incl. ditches	1500		6500											
3	223	Regravelling, 15.0 cm thick														
4	125	Spot filling			200											
5	133	Cleaning of culverts				1										
6	135	Repair of erosion damages			75											
			Ch. (km 12+500 - km 14+000)													
ခ/၀	MAC	Description	12+500	13+000	13+500	14+000										
1	121	Haevy grading														
2	222	Reshaping the road, incl. ditches	1500		4000											
3	223	Regravelling, 15.0 cm thick														
4	125	Spot filling			100											
5	133	Cleaning of culverts				1										
6	135	Repair of erosion damages				50										

Supplementary Information

The attached map shown the locations of candidate roads included in the contract